

**Town: Montague**  
 Date: January 27, 2017, Revised 2/24/17



MBI Area #	Street Name	Location description	a) Aerial Mileage	a) UG Mileage	Residential Standard Installation	b) Residential over 300'	Commercial Premise	Total Passings	a) Total Miles	c) HPM	d) Spans	Map #
145	Chestnut Hill Loop	From the c/o East Chestnut Hill Rd (pole 27/3/33) southeast to c/o Richardson Rd (pole 27/NT/10) and then 2 spans on Richardson Rd. to feed house #8	0.4	0.0	2	0	0	2	0.4	5.0	9	413-416 414-415 414-416
146	Chestnut Hill Loop	From the c/o East Chestnut Hill Rd (pole 27/28/30) south and then west to c/o Richardson Road (pole 27/NT/10).	0.6	0.0	8	2	0	10	0.6	13.3	20	413-416 414-416 415-416
147	East Chestnut Hill Rd	From pole 14/22/54-15 at Leverette town line north to end of pole line (pole 27/29-5) at house #199	1.4	0.0	10	17	0	27	1.4	7.1	34	413-414 413-415 414-415 415-415 415-416 416-416
148	West Chestnut Hill Rd	From pole 25/1/38 on North Leverett Rd (in town of Leverett) north and east to pole 27/1/31 near E Chestnut Hill Rd	1.5	0.0	10	6	2	18	1.5	6.7	44	413-413 413-414 414-414 414-415 415-414 415-415
149	Leverett Rd	From pole 25/1/38 at c/o W Chestnut Hill Rd (in town of Leverette) west to c/o Ripley Rd at pole #151/31/22 in Montague	0.3	0.0	7	0	0	7	0.3	23.3	7	413-413
151	Ripley Rd	From pole 151/31/22 at c/o N Leverette Rd north to end of pole line at pole #165/24 to feed house #82	0.9	0.0	10	0	2	12	0.9	11.1	24	413-412 413-413 414-412
152	Ripley Rd	Extend underground plant from pole 151/31-1 at the intersection of Spaulding Brook on Ripley Rd for .2 miles, feeds 1 home, 1 commercial	0.1	0.2	1	0	0	1	0.3	4.0	1	413-413
152-1	Dry Hill Rd	From existing cable termination at pole 23/5 on westside of railroad tracks, east to end of pole line at pole 52/37 to feed house #155. Includes Hannabrook Ln	1.4	0.0	17	7	1	25	1.4	12.1	36	419-412 419-413 419-414
152-2	W. Mineral Rd	From existing cable termination at pole 189/68, north to the end of pole line at house 98 (pole 202/18 / 19/24).	0.7	0.2	7	0	0	7	0.9	7.7	18	427-412 428-413 429-413

**Town: Montague**  
 Date: January 27, 2017, Revised 2/24/17



MBI Area #	Street Name	Location description	a) Aerial Mileage	a) UG Mileage	Residential Standard Installation	b) Residential over 300'	Commercial Premise	Total Passings	a) Total Miles	c) HPM	d) Spans	Map #
152-3	Taylor Hill Rd	From existing termination at pole 35/24, south to the c/o Old Sunderland RD (Pole 15).	0.5	0.0	5	0	0	5	0.5	9.3	13	415-409 414-409 413-409
152-4	Old Sunderland Rd	From existing cable termination at pole 35/4, south to the end of pole line (pole 129/27) at house #123.	0.4	0.0	2	0	0	2	0.4	5.6	9	415-410 414-410
152-5	Old Sunderland Rd	From the c/o of Taylor Hill Rd (pole 15), north for one span to the end of pole line at pole 15-1. Then, from the c/o Taylor Hill Rd, south for two spans to the end of pole line at pole 13/39.	0.1	0.4	3	1	0	4	0.5	5.9	3	413-409
152-6	Old Sunderland Rd	From pole 13/39 near Taylor hill Rd, underground south for 2041' to tie to pole at house 199, then 3 more spans to house 209. Note, this area cannot be served from Sunderland because it is fed from the Deerfield Head End. Also, the existing plant in Sunderland is at its maximum amp cascade. This area needs to be fed from the north out of our Montague Head End for telephony services.	0.1	0.4	2	1	0	3	0.5	3.9	3	413-409 412-409
152-7	N. Leverett Rd	From existing cable at pole 11 / 22/40/10, east to the c/o Spaulding Brook Rd (pole 151/31 / 22).	1.0	0.0	6	0	1	7	1.0	5.9	23	414-411 414-412 413-413 413-412
152-8	Wendell Rd	From existing cable termination at pole 48/52 at the c/o Dry Hill Rd, south to the c/o E. Chestnut Hill Rd (pole 62/65).	0.9	0.0	5	1	1	7	0.9	5.8	14	421-417 420-417 419-417
152-9	E. Chestnut Hill Rd	From the c/o Wendell Rd (pole 62/65), south to the end of pole line (pole 8/74) at house 301 and 302.	0.5	0.0	8	0	0	8	0.5	16.0	10	420-417 419-417 418-417
152-10	Taylor Heights Rd	From existing cable termination at pole 4, east to the end of pole line that feed house 15, 17, 21	0.3	0.0	3	0	0	3	0.3	12.0	8	416-409 416-410 415-410
152-11	Fosters Rd	From existing plant at the c/o Sunderland Rd / rte 47 (pole5/51), west to the end of pole line (pole7) at house #33	0.3	0.0	2	0	0	2	0.3	6.7	7	413-410
<b>Design Totals</b>			<b>11.3</b>	<b>1.2</b>	<b>108</b>	<b>35</b>	<b>7</b>	<b>150</b>	<b>12.5</b>	<b>8.6</b>		
<b>Minimum number of premises per 8/17/16 agreement (96%)</b>			<b>9.6</b>	<b>0.4</b>	<b>95</b>	<b>9</b>	<b>1</b>	<b>105</b>	<b>10.0</b>	<b>9.5</b>		
<b>Variance</b>			<b>1.7</b>	<b>0.8</b>	<b>13</b>	<b>26</b>	<b>6</b>	<b>45</b>	<b>2.5</b>			

**Town:** Montague  
 Date: January 27, 2017, Revised 2/24/17



MBI Area #	Street Name	Location description	a) Aerial Mileage	a) UG Mileage	Residential Standard Installation	b) Residential over 300'	Commercial Premise	Total Passings	a) Total Miles	c) HPM	d) Spans	Map #
<b>Areas Outside of MBI Build Territory</b>												
A	Wills Ferry Rd	From existing cable termination at pole 688/35 / 7, west to the end of pole line (pole 68 - 40 / 12) at house #44.	0.4	0.0	2	0	0	2	0.4	5.6	5	419-409
B	Greenfield Rd	From existing cable termination at pole 62P / 91 / 1/21, north to the end of pole line (pole 72/83) at house 191	0.3	0.0	2	0	0	2	0.3	6.7	9	423-409 424-409 425-409
C	E. Mineral Rd	From existing plant at the c/o Millers Falls Rd (pole 6/1), north to the end of pole line at house #93 (pole 31-4 / 27-9).	0.6	0.0	2	0	0	2	0.6	3.3	14	426-413 427-413
D	E. Mineral Rd	From last pole in Area C (pole 31-4 / 27-9), underground for 2400' to tie to pole 54 3-3, then aerial to the town line (pole 54-1 / 27)	0.3	0.5	3	0	1	4	0.8	3.8	5	427-413 428-413 428-414 429-414
E	Mormon Hollow Rd	From Existing Plant at pole 1978/31 / 35 on Wendell Rd, south, then east to the end of pole line (pole 42/49) at the Wendell town line. Includes one pole span od Davis Rd	0.7	0.0	6	1	0	7	0.7	8.2	13	424-416 423-416 424-417
F	Easement to Reservoir Office	From existing plant on Lake Pleasant Rd (pole 69/20), east to pole 115/15-4 at Reservoir Office.	0.2	0.0	0	0	1	1	0.2	0.0	4	423-412 423-413
G	Ripley Rd and Highland Rd	From existing cable on the west side of the railroad tracks (pole 91/5), cross tracks and end at pole 11-4 / 15 on Ripley Rd. Will require easement on farm property and 273' ug.	0.4	0.0	3	0	0	3	0.4	7.3	10	416-412 415-412
H	Ripley Rd	From existing cable termination at pole 2/2, southeast to 214/8 at house 28	0.2	0.0	2	1	1	4	0.2	10.0	6	416-411 415-411
I	West St	From the c/o School St, west to the end of pole line (pole 8). One commercial business (no number) at the end of street will require 2044' of underground to the building.	0.2	0.4	2	2	2	6	0.6	3.4	6	416-410 417-410
J	Federal St	From existing cable termination at pole 67-6 / 14, underground for 446' to the town line to feed house #617. This will require a railroad crossing under bridge.	0.0	0.1	1	0	0	1	0.1	12.5	0	413-411 412-411
<b>Total</b>			<b>3.3</b>	<b>1.0</b>	<b>23</b>	<b>4</b>	<b>5</b>	<b>32</b>	<b>4.2</b>	<b>5.4</b>		

**Notes**

- a) Mileage is based on original field odometer ride out. Final mileage true-up will be completed from "As-built" documentation.
- b) Homes requiring a construction contribution
- c) Includes standard residential passings only
- d) Does not include drop only poles that are being licensed. Spans on private property.